Bakken Well Factory and the Importance of Local Roads February 2023







Introduction to Hess

- Bakken Development Overview of Below Surface Operations
- Surface Activity and Road Usage Summary for New Well Development
 - Construction Activity
 - Rig Moves and Drilling Operations
 - Frac Moves and Frac Operations
- How Do We Minimize Our Impact to Roads?

2023 Operations at a Glance





Hess Leading Acreage Position in the Bakken

Growing production while being a role model for our community



- Long history in basin; focus on core acreage with stable existing production and substantial future drilling inventory
 - Drilled first well in 1951; ~\$8 billion invested in last 5 years
 - Operating in ~460,000 net acres;
 - ~1,600 Hess operated wells / support; ~1,500 non-op wells
 - ~1,800 future Hess locations, 60+ rig years at \$60 WTI
 - ~80% of recoverable resources yet to produce

Increasing activity to grow production

- 4th rig added July '22; expect to maintain program
- 4 rigs grows net production to 200 MBOEPD
- Planning to spend ~\$1.1 billion in 2023; ~110 new wells online

Sustainable practices create value for all stakeholders

- Environmental risks can be addressed while still providing safe, affordable and reliable energy
- Actively working to reduce our operational GHG emissions focusing on reducing flaring and improving total gas capture
- Committed to eliminating routine flaring by year-end 2025



Overview of How We Develop the Bakken

Drilling to wells online and how it connects below the surface





API (Energy From Shale). (2023, January 18th), Hydraulic Fracturing [Video]. Hydraulic Fracturing - YouTube

Bakken Asset Well Factory

Life cycle of well extends to 40+ years





Well Pad & Facility Construction

What does it take to Plan and Build a Pad and Facility for New Bakken Well



6 months to complete surface well planning

- Survey (topographic and environmental), design, land agreements, permits
- Longer for wells that require federal permits
- Up to 2 years ahead of planned drilling date
- 30 days for pad construction
 - Earthwork, underground flowlines, surfacing
- 20 days for new facility construction
 - Facility build
 - *Excludes pipeline scope

Activity	Approximate Impact
Civil Construction Loads	120 loads (5 permitted)
Facility Construction Loads	20 loads (5 permitted)
Heaviest Load	100,000 lbs.
Count of people on site	5 - 25



Drilling Operations and Moves

What does it take to drill a Bakken Well?

- 12.5 days per well (was 30 days in 2012)
 - Average duration per well includes rig up, drilling wells, rig walks, rig down
- 7 days for drilling the vertical and curve
- 5 days for drilling horizontal
- .5 days to walk from well to well
 - Rig "walks" 33' from well to well
- 5 days for rig move from site to site

Activity	Approximate Impact
Move in rig	95 loads (40 permitted)
Total weight of equipment	1,844,000 lbs. (Rig)
Heaviest Load	93,000 lbs.
# of trucks during operations per well (casing, cement, cuttings, fuel)	45/well
# of trucks for rig move	25
Count of people on site	20-50





8

Completions Operations and Moves

What does it take complete a Bakken well?

- Completions includes Frac, Coil Tubing, Flowback
- 3.5 days per well for a frac
 - Pumping water and proppant downhole
- 2 days per well for coil tubing
 - "Cleaning out" well
- 10 days per well for Flowback
 - Initial production of the well

Activity	Approximate Impact
Move in frac equipment	76 (36 permitted)
Total weight of equipment	4,700,000 lbs (Frac Equipment)
Heaviest Load	98,500 lbs
# of trucks during operations	28/well
# of people on location during operations	74
# of sand trucks	245/well
# number trucks required if water is not piped into location	2220/well





Process from Start to Well Producing

Timelapse of how it all comes together...



Mitigating the Impacts to the Roads Where we Operate

What does Hess do from planning to execution to minimize our impact?



Upfront planning

- Development plans
 - Well planning
 - Multi-batch pads
 - Extended laterals
 - Utilizing existing infrastructure (including roadways)
 - Constructed/Improved roughly 4 miles of public roadway in 2021 and 2022
- Development schedules
 - Rig move and frac timing
 - Planning around county road projects

Operational changes

- Water handling during completions
- X-rigs
 - More divisible than other rigs
 - Moving rigs from generator power to line power
- Production volumes from truck to pipelines

Example of multi-well batch pads



Example of extended lateral development





Extensive process to develop a Bakken well

There is efficient traffic associated with Bakken well development

Pad/Facility Construction, Drilling and Completions

Things we do to help reduce our impact on roadways

- Planning
- Operational improvements



Typical Well Pad Facility Layout

6



Typical Layout

1. Flare

- 2. Separation Vessel/Skid
- 3. Production Tanks (oil and produced water)
- 4. Pipeline Tie-Ins
- 5. Producing Wells
- 6. Site Containment ditch and Controlled Stormwater Discharge

Typical Frac Layout





Typical Rig Layout

2

6



Typical Layout

- 1. Drill Floor
- 2. Mud Pits/ Tanks
- 3. Generators and Mud Pumps
- 4. Drilling Fluid Storage Tanks
- 5. Safety Trailer and Crew Quarters
- 6. Tubular Handling Equipment
- 7. Solids Control Area